

**FAC 8321 Sewer and Industrial Waste Line**

RUC: \$32.77 LF

Source: Marshall and Swift  
 Inflated to FY-09 using Green Book Table 5-6 (MCON)  
 In V12, Tri-Service and USACE PAX Newsletter values were updated while all other values were inflated only.

Calculation follows:

8321	Sewer and Industrial Waste Line		Average Cost			Adjustments		
	66/1	8" asbestos cement	Lo	Hi	Ave	Current	DC	
	Dec 07		0		21.25			
						1.03	1.03	22.54
		sewer manhole, 400' o.c.			2580			
		per linear foot			6.45	1.03	1.03	6.84
		sewer cleanout, 100' o.c.			700			
		per linear foot			7.00	1.03	1.03	7.43
		decrease cleanouts for manhole at 400 foot						5.57
					TOTAL Per Linear Foot			34.96

SUC: \$1.65 LF

Source: Inflated from V10  
 Association of Metropolitan Sewage Agencies, 2002 data  
 Actual inflation applied from 2002 to 2008 using ENR composite index  
 Inflation from FY-08 to FY-09 projected using Green Book Table 5-6 (O&M less DHP)  
 In V12, values were inflated only.